

NZCB Verification Report

Project Name:	Leicester Distribution Park, Phase 3	
Date of assessment	25/02/2022	
Verified by	Sarah Howe	
Project type	New build	
Assessment objective	To determine the total carbon contribution of the development and offset to ensure the result of the development is Net Zero Carbon at practical completion.	
Project location	Unit A-C, Liliput Road, Brackmills Industrial Estate, Northamptonshire, NN4 7EY	
Date of project completion	19 th September 2022	
Property type	Warehouse	
Building description	industrial buildings with associated office areas and hard landscaping	
Size	 Unit 2 GIFA – 13,967 m² (contract = 13,935m²) Unit 6 GIFA – 4,242 m² (contract = 4,181m²) Unit 7 GIFA – 2,819 m² (contract = 2,787m²) Unit 8 GIFA – 7220 m² (contract = 6,968m²) 	
Project design life	60yrs	
Assessment scope	Shell and Core	
Assessment stage	As built	
Data Sources	As built drawings and specifications	

Assumptions & Scenarios

2no. runs (primary & secondary siphonics) per each gutter / valley, plus 2no. runs at each gable end, plus 2no. downpipes at each corner of the building.





- +44 (0)333 242 2933
- bello@greenboxthinking.com
 index
 index
- greenboxthinking.com



NZCB VERIFICATION REPORT

Verification Statement

This verification has been conducted in accordance with RICS Methodology and EN 15978

I hereby confirm that, following detailed examination, I have not established any relevant deviations by the studied Life Cycle Assessments:

- o the underlying data collected and used in the LCA calculations,
- o the way the LCA-based calculations have been carried out,
- o the presentation of environmental performance included in the EPD, and
- other additional environmental information included in the declaration, if existent with respect to the procedural and methodological requirements in ISO 14025:2010 and EN 15804:2011.

Company-specific data has been examined as regards plausibility and consistency; the declaration owner is responsible for its factual integrity and that the product does not violate relevant legislation.

I confirm that I have sufficient knowledge and experience of construction products, the construction industry, relevant standards and the geographical to carry out this verification.

I confirm that I have been independent in my role as verifier; I have not been involved in the execution of the LCA or in the development of the declaration and have thus no conflicts of interest regarding this verification.

Name:	Sarah Howe	
Signature:	2000	
Date:	25/02/2022	







hello@greenboxthinking.com

greenboxthinking.com





Building Elements Coverage

#	Building Parts / Element Groups	Building Elements	Coverage (%)
0	Facilitating works	0.1 Temporary/Enabling works/Preliminaries	0
	-	0.2 Specialist groundworks	0
1	Substructure	1.1 Substructure	27.06
		2.1 Frame	9.83
	Substructure	2.2 Upper floors incl. balconies	2.22
	00.001.0010.0	2.3 Roof	11.48
2		2.4 Stairs and ramps	0.47
_	Superstructure	2.5 External Walls	6.99
	Caporotractare	2.6 Windows and External Doors	1.61
	Superstructure	2.7 Internal Walls and Partitions	0.76
	Caperstructure	2.8 Internal Doors	0.02
	Finishes	3.1 Wall finishes	0.09
3		3.2 Floor finishes	1.58
		3.3 Ceiling finishes	0.6
4	Fittings, furnishings and	Building-related	0
4	equipment (FF&E)	Non-building-related	0
5	Building services / MEP	5.1–5.14 Building-related* services	1.36
3	Building Services / IVILE	Non-building-related	15.68
6	Prefabricated Buildings and Building Units	6.1 Prefabricated Buildings and Building Units	0
7	Work to Existing Building	7.1 Minor Demolition and Alteration Works	0
	External Works	8.1 Site preparation works	0
		8.2 Roads, Paths, Pavings and Surfacings	19.66
		8.3 Soft landscaping, Planting and Irrigation Systems	0
8		8.4 Fencing, Railings and Walls	0
		8.5 External fixtures	0.57
		8.6 External drainage	0
		8.7 External Services	0
		8.8 Minor Building Works and Ancillary Buildings	0









greenboxthinking.com

☆ Concordia Works 30 Sovereign Street Leeds LS1 4BA




NZCB VERIFICATION REPORT

Embodied Carbon

Indicator	Amount
Total embodied carbon (tCO ₂) from construction (modules A1 to A5 of EN15978) at practical completion / Total whole life carbon (kgCO2e/m²) from construction (modules A1 to A5 of EN15978)	11,729 / 510
Total embodied carbon offset (tCO2e) at practical completion	11,729
Net embodied carbon (tCO2e) at practical completion	0

Carbon Offsets

Carbon offset approach used	Minimum / Leadership Transition Fund
International carbon offset standard used, amount and type of offset credit procured	11,729 credits in VERRA VCS, across REDD+ and renewable energy projects
Registry link	https://registry.verra.org/myModule/rpt/myrpt.asp?r=206&h=163366
	https://registry.verra.org/myModule/rpt/myrpt.asp?r=206&h=163368
	https://registry.verra.org/myModule/rpt/myrpt.asp?r=206&h=163365
	https://registry.verra.org/myModule/rpt/myrpt.asp?r=206&h=166291
	https://registry.verra.org/myModule/rpt/myrpt.asp?r=206&h=163370
	https://registry.verra.org/myModule/rpt/myrpt.asp?r=206&h=156571
Domestic carbon unit standard used, amount and type of offset unit procured	n/a
Weighted average cost per tonne of CO2e for carbon credits/units bought	£5 - £25
Transition Fund – carbon price, cost per tonne of CO2e (if applicable)	n/a



hello@greenboxthinking.com

greenboxthinking.com